

1 080247

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,152-*cccc*

NE NE NW , SEC. 4 , T 35 S, R 15 W/E  
4950 feet from N SE Corner of  
3180 feet from W SE Corner of  
W/E section line  
W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Z-Bar Cattle Well # "A" 1  
Company

Operator: TXO Production Corp.

County Barber

Name & Address 200 West Douglas, Suite 300

Well Total Depth 5010 *162.83* feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 430

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Clarke Oilfield Services License Number 5105

Address 107 West Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 12:30 pm Day: 30 Month: October Year: 19 84

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" set at 5009' PBTD 4999' Perfs at 4956-66'

1st plug sand back to 4906' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,  
and 125 sx cement

RECEIVED  
STATE CORPORATION COMMISSION  
11-8-84  
NOV 08 1984

Plugging Proposal Received by J. H. Metz

(TECHNICIAN)  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:30 pm Day: 30 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 5009' PBTD 4999' Perfs at 4956-66'

1st plug sanded back to 4906' and dumped 4 sx cement on top of sand through bailer,

2nd plug squeezed well with 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,  
and 125 sx cement.

Maximum pressure 500 psi and shut in pressure 300 psi

Remarks: Recovered 3491' 4 1/2" casing Used Common cement 2% cc.

(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

Signed

*J. H. Metz*  
(TECHNICIAN)

*[Signature]*

DATE 11-14-84

INV. NO. 4733