

To: 1 041242 4-18
STATE CORPORATION COMMISSION
Wichita, State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-007-21,151-0000
NW NW SW, SEC. 2, T 35 S, R 15 W/E
2310 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5506
Operator: Woolsey Petroleum Corporation
Name &
Address 107 N. Market, Ste. 600
Wichita, KS 67202

Lease Name Z-Bar Well # B-1
County Barber 161.53
Well Total Depth 4970 feet
Conductor Pipe: Size 16 feet 60
Surface Casing: Size 8 5/8 feet 416
Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated _____
Plugging Contractor Clarke Corporation License Number 5105
Address Medicine Lodge, KS

Company to plug at: Hour: 10:30 a.m. Day: 18 - Month: 4 Year: 19 97
Plugging proposal received from Alan Vratil
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4972' w/175 sx cement, PBSD 4947', Perfs at 4910-18, 4902-08'
1st plug sand back to 4850' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

RECEIVED
KANSAS FOR
CORRECTION
197 APR 22
4-22-97

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 11:15 a.m. Day: 18 Month: 4 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4754' and dumped 4 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, and 100 sx cement.
Maximum pressure 100 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3400' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 4-24-97

Signed Stephan J. Penfer
(TECHNICIAN)

INV. NO. 48011

Schlumberger

DUAL INDUCTION-SFL
WITH LINEAR CORRELATION LOG

COUNTY FIELD LOCATION WELL COMPANY	COMPANY	TEXAS OIL & GAS CORP.			
		15-007-21151-0000			
	WELL	Z-BAR CATTLE 'B' #1			
	FIELD	AETNA			
	COUNTY	BARBER		STATE	KANSAS
	LOCATION				Other Services: FDX - CNL - GR
	API SERIAL NO.	SEC.	TWP	RANGE	
		2	35S	15W	

Permanent Datum:	GROUND LEVEL	Elev.:	1538
Log Measured From	KB		12 Ft. Above Perm. Datum
Drilling Measured From	KB	Elev.:	K.B. 1550
		D.F.	
		G.L.	1538

Date	5-11-81				
Run No.	one				
Depth-Driller	4970				
Depth-Logger	4973				
Btm. Log Interval	4973				
Top Log Interval	1900				
Casing-Driller	8518 @ 416		@	@	@
Casing-Logger	416				
Bit Size	7718				
Type Fluid in Hole	DAVIS				
Dens.	Visc.	9.0	56		
pH	Fluid Loss	10.5	12.8 ml	ml	ml
Source of Sample	CIRCULATED				
Rm @ Meas. Temp.	.819 @ 55 °F	.392 @ 115 °F	@ °F	@ °F	@ °F
Rmf @ Meas. Temp.	.216 @ 66 °F	.124 @ 115 °F	@ °F	@ °F	@ °F
Rmc @ Meas. Temp.	— @ — °F	@ °F	@ °F	@ °F	@ °F
Source: Rmf Rmc	M —				
Rm @ BHT	.392 @ 115 °F	@ °F	@ °F	@ °F	@ °F
TIME	Circulation Stopped	01:00			
	Logger on Bottom	05:00			
Max. Rec. Temp.	115 °F		°F	°F	°F
Equip.	Location	7747	Wichita		
Recorded By	BAUER		SMITH		
Witnessed By	G VEATCH				

The well name, location and borehole reference data were furnished by the customer.

FOLD HERE