

To: 1 010005
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,678-0000

SW NE NE, SEC. 3, T 30 S, R 13 W EX

4290 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5035

Lease Name Tregellas Well # 3

Operator: Aladdin Petroleum Corp.

County Barber 152.75

Name & Address 809 Petroleum Building,

Well Total Depth 4700 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 13 3/8" feet 295

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:25 am Day: 12 Month: July Year: 19 85

Plugging proposal received from Bill Fulls

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4697' Perfs at 4324-27'; 4327-29'; 4329-31'; 4331-33'; 4554-56'; 4556-58'

1st plug run 20 bbls salt water to kill small amount of gas.

2nd plug sand back to 4275' and dump 4 sx cement on top of sand through bailer

3rd plug squeeze well with 4 sx hulls, 25 sx gel, 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel 1 sack hulls, release 13 3/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:15 pm Day: 12 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug ran 20 bbls salt water to kill small amount of gas, 2nd plug sanded back to 4275' and dumped 4 sx cement, 3rd plug squeezed well with 3 sx hulls 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 13 3/8" rubber plug and pumped 200 sx cement.

Maximum pressure 400 psi and shut in 300 psi

Remarks: Recovered 2305' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 7-24-85
INV. NO. 9079

Signed [Signature] (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
AUG 22 1985
CONSERVATION DIVISION
Wichita, Kansas

