

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22240-00-00
Spot: CNWNE Sec/Twnshp/Rge: 5-30S-13W
4620 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: LAMBERT A Well Number: 2
County: BARBER Total Vertical Depth: 4810 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

Conductor Pipe: Size feet: 4 5/8 33
Surface Casing: Size 10.75 feet: 275 WITH 200 SX CMT
Production: Size 5.5 feet: 4808 WITH 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/27/2002 12:00 PM

Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: VERNON PFLUGHOEFT Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: SAND BACK TO 4570' & 5 SX CMT. 1ST PLUG AT 800' WITH 50 SX CMT. 2ND PLUG AT 315' WITH 60 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER
Date/Time Plugging Completed: 03/27/2002 1:30 PM

WitnessType: Plugging Operations 100% Witnessed (Complete)
KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4775'. PERFS AT 4621-4625'. SANDED BACK TO 4550' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 800' WITH 450# HULLS - 11 SX GEL - 50 SX COMMON CMT WITH 3% CC. 2ND PLUG AT 305' WITH 60 SX 60/40 POZMIX 6% GEL. 3RD PLUG AT 40' WITH 20 SX 60/40 POZMIX 6% GEL. TOP OFF 10 3/4" SURFACE PIPE WITH 10 SX CMT. 03/28/02: TOP OFF 10 3/4" SURFACE PIPE WITH 50 SX CMT.

RECEIVED
KANSAS CORPORATION COMMISSION
APR - 9 2002
4-9-02
CONSERVATION DIVISION

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID & CEMENTING. RECOVERED 2400' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED APR 02 2002

DATE 4-10-02

INV. NO. 2002061633

Form SP-33