

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22230-00-00
Spot: W2NENE Sec/Twnshp/Rge: 5-30S-13W
4620 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: LAMBERT B Well Number: 1
County: BARBER Total Vertical Depth: 4800 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

Conductor Pipe: Size feet: 8156.00
Surface Casing: Size 8.625 feet: 310 WITH 195 SX CMT
Production: Size 5.5 feet: 4799 WITH 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/25/2002 11:00 AM

Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: VERNON PFLUGHOEFT Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: SAND TO 3950' & 5 SX CMT. 1ST PLUG AT 800' WITH 50 SX CMT. 2ND PLUG AT 340' WITH 50 SX CMT. USE 10 SX GEL FOR SPACER.

Plugging Proposal Received By: STEVE MIDDLETON

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 03/26/2002 2:45 PM

KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PBTD 4775'. PERFS AT 4610-14 & 4614-18'. ON 03/25/02: SAND BACK TO 4540' WITH 5 SX CMT ON TOP WITH BAILER. SPOT 10 SX GEL & 50 SX 60/40 POZMIX 6% GEL AT 800'. NO CIRCULATION. PULL TO 340' & PUMP 25 BBL WATER. NO CIRCULATION. CHECK FLUID LEVEL. FL AT 250'. PUMP 10 BBL WATER. CHECK FL. FL AT 250'. PUMP 500# HULLS AND 5 SX GEL. NO CIRCULATION. PULL CASING. SDON. ON 03/26/02: RAN 2 7/8" TUBING TO 1037'. NO CMT. PULLED TO 809'. PUMPED 10 SX GEL, 500# HULLS, & 50 SX COMMON CMT WITH 3% CC. WAIT ON CMT 1 HOUR. TAGGED CMT AT 809'. PULLED TO 339' & PUMPED 50 SX COMMON CMT WITH 3% CC. NO CIRCULATION. WAIT 1 HOUR ON CMT. TAG CMT AT 345'. PULLED TUBING TO 280'. ESTABLISHED CIRCULATION WITH 5 BBL WATER. PUMPED 25 SX COMMON CMT WITH 3% CC AT 280'. GOOD CIRCULATION. PULLED TUBING TO 40' & PUMPED 10 SX COMMON CMT. GOOD CIRCULATION.


RECEIVED
APR 01 2002
4-1-02
KCC WICHITA

Remarks: USED COMMON CMT WITH 3% CC BY COPELAND ACID & CMT. RECOVERED 2360' OF 5 1/2" CASING.

Plugged through: TBG

District: 01

Signed


(TECHNICIAN)

INVOICED

DATE 4-2-02

INV. NO. 2002061597

MAR 28 2002

Form 10/03

