

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22203-00-00
Spot: CNESWNE Sec/Twnshp/Rge: 5-30S-13W
3630 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: LAMBERT A Well Number: 1
County: BARBER Total Vertical Depth: 4770 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

Conductor Pipe: Size _____ feet: 8/55.03
Surface Casing: Size 10.75 feet: 332 WITH 225 SX CMT
Production: Size 4.5 feet: 4767 WITH 50 SX CMT
Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/28/2002 11:45 AM

Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: VERNON PFLUGHOEFT Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: SAND BACK TO 4575' & 4 SX CMT. 1ST PLUG AT 800' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 60 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER
Date/Time Plugging Completed: 03/28/2002 2:15 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 4625-4633'. SANDED BACK TO 4575' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH CASING. 1ST PLUG AT 800' WITH 550# HULLS - 15 SX GEL - 50 SX COMMON CMT WITH 3% CC. 2ND PLUG AT 360' WITH 60 SX 60/40 POZMIX 6% GEL. 3RD PLUG AT 40' WITH 20 SX 60/40 POZMIX 6% GEL.

RECEIVED
KANSAS CORPORATION COMMISSION
APR - 9 2002
4-9-02
CONSERVATION DIVISION

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID & CEMENTING. RECOVERED 2125' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED APR 02 2002

DATE 4-10-02

INV. NO. 2002061633

Form 02-1/3