

1 010235

APR 2 2 1987

159

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,760-0000

SW SW NE, SEC. 5, T 30 S, R 13 W/E

3380 feet from S section line

2530 feet from E section line

Lease Name Hildreth Well # 1-5

County Barber 154.70

Well Total Depth 4760 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 302

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Operator: F.G. Holl Estate
Name & Address
P.O. Box 780167
Wichita, KS 67267

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service Inc. License Number: 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 10:40 a.m. Day: 22 Month: 4 Year: 19 87

Plugging proposal received from Fred Mease

(company name) Pratt Well Service (phone) 1-800-362-0597

were: 4 1/2" at 4780' PBD 4626' Perfs at 4611-19'

1st plug sand back to 4508' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 135 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 22 Month: 4 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4500' and dumped 4 sx common cement on top of sand through bailer,

2nd plug pumped 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 135 sx cement - 60/40 Pozmix 6% gel.

Maximum pressure 550 psi and shut in 350 psi.

Remarks: Recovered 3573' of 4 1/2" casing. Used common cement and 60/40 Pozmix 6% gel by Hall-
(if additional description is necessary, use BACK of this form.) iburton.

INVOICED

STATE CORPORATION COMMISSION

APR 28 1987

Signed Jack P. Luthi
(TECHNICIAN)

DATE 4-29-87

INV. NO. 16670

CONSERVATION DIVISION
Wichita, Kansas