

To: 1 040757
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-8

API NUMBER 15- 007-01,026-00-02
C NE SE, SEC. 5, T 30 S, R 13 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

1980 feet from S section line
660 feet from E section line

Operator: F.G. Holl Company

Lease Name Lambert 2C Well # 1-5

Name:

County Barber

Address P.O. Box 780167

Well Total Depth 4809 156.29 feet

Wichita, KS 67278-0167

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 461

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service, Inc. License Number 5883

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10 a.m. Day: 8 Month: 6 Year: 19 93

Plugging proposal received from Tom Pool

(company name) F.G. Holl Co. (phone) 316-995-3171

were: 5 1/2" at 4809', PBSD 4798', Perfs at 4399-4403, 4560-65; 4546-60'

1st plug sand back to 3989' and dump 5 sx cement on top of sand bridge through bailer,

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11 a.m. Day: 8 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 3989' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Maximum pressure 250 psi and shut in 140 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2283' of 5 1/2" casing. If additional description is necessary, use BACK of this form.)

(did / ~~did not~~) observe this plugging.

DATE 6-22-93

WV. NO. 37980

Signed Stephen C. Plifer (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JUN 16 1993
6-19-93
CONSERVATION DIVISION
Wichita, Kansas