

*10*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

SEP 10 1964  
9-10-64  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Gensch and Holke

Complete Address: 1527 Wichita Plaza, Wichita, Kansas

Lease Name Means Well No. # 1

Location C SW SW Sec. 32 Twp. 30 Rge. 12 (E) (W) W

County Barber Total Depth 3905

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Leben Drilling Inc.

Address: 912 Central Bldg., Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 10:00AM Day 9th Month Sept. Year 1964

The Above well was plugged as follows:

215' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole was  
filled with drilling mud to 215', 1st cementing plug, bridged solid with  
hulls, on fluid at 215', and cemented with 25 sacks. Hole was filled  
with drilling mud to 40', 2nd cementing plug, bridged solid with hulls,  
on fluid at 40', and cemented with 10 sacks to the base of the cellar.  
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

DATE 9/10/64  
INV. NO. 9488-u

Signed: Archie Elving  
Well Plugging Supervisor