

Y
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
1-11-68
JAN 11 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued December 15, 1967.

Operator's Full Name Shenandoah Oil Corporation

Complete Address: 1018 Commerce Bldg., Fort Worth, Texas 76102

Lease Name Lulu Sleeper Well No. # 1

Location App. C SE ^{NW} NE Sec. 25 Twp. 30 Rge. 11 (E) (W) W

County Barber Total Depth 4793'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Clarke Corporation, Inc.

Address: Chapin Bldg., Medicine Lodge, Kansas License No. 583

Operation Completed: Hour 2:30PM Day 6th Month January Year 1968

The Above well was plugged as follows:

273' of 8 5/8" surface pipe, cement circulated. 4791' of 4 1/2" long string,
cemented with 140 sacks. Top perferation 4749'. 15 sacks of cement was pumped
on bottom, with the top of the cement at 4716'. 3950' of 4 1/2" long string was
recovered from the hole. Fluid in the hole was bailed down to 250', rock
bridge from 250' to 240', and cemented with 25 sacks, with cement from 240'
to 165'. Hole was filled with mud to 40', rock bridge from 40' to 30', and
cemented with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 1/11/68
INV. NO. 7078-W