



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

SEP 9 1963  
 9-9-63  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. James Shipley of Graybol Oil Corporation has this date requested permission to plug the following described well:

Mr. Shipley guarantees payment of the plugging fee.

Operator's full Name: Graybol Oil Corporation

Complete Address: 2200 National Bank of Tulsa, Tulsa, Oklahoma

Lease Name: Lambert Well No. # 1

Location: C NE SE Sec. 5 Twp. 30 Rge. 13 (E)(W) W

County Barber Total Depth 4800 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Shipley was instructed to plug the well as follows:

460' of 8 5/8" surface pipe, cemented with 275 sacks.

Fill hole with mud to 300', 1st cementing plug, 1/4 sack hulls,

cement with 20 sacks. Fill hole with mud to 40', 2nd cementing

plug, 1/4 sack hulls, cement with 10 sacks to base cellar.

Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent