



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

August 16, 1963

RECEIVED
STATE CORPORATION COMMISSION

AUG 21 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Ed Walker of Garvey Drilling Co. has this

date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name: Wharton Well No. 1

Location: Approx. SE NE Sec. 30 Twp. 19 Rge. 8 (E) (W) X

County Rice Total Depth 3452' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

Circulate heavy mud. Fill hole with mud to 210'. Push
plug and 1/4 sack hulls to 210' and cement with 20 sacks
through drill pipe. Fill hole with mud to 40'. Push plug
and 1/4 sack hulls to 40' and cap hole with 10 sacks cement.
Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent