



15-159-30176-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

November 26, 1965
RECEIVED
STATE CORPORATION COMMISSION

NOV 29 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Joe Gerritzen of Braden Drilling, Inc. has this
date requested permission to plug the following described well:

Mr. Gerritzen guarantees payment of the plugging fee.

Operator's full Name: Wayne Merchant

Complete Address: 227 Beacon Bldg., Wichita, Kansas

Lease Name: Blessing Well No. 15

Location: Approx. C NW NE Sec. 33 Twp. 19 Rge. 8 (E) (W) X

County Rice Total Depth 3410' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gerritzen was instructed to plug the well as follows:

Fill hole with mud to 200'. Push plug and 1/4 sack hulls to
200' and cement hole with 25 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and 1/2 sack hulls to
40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,

Richard J. Roman
Conservation Division Agent