



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

September 2, 1963

SEP 9 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. D. B. Livingston of Pickrell Drilling Co. has this date requested permission to plug the following described well:

Mr. Livingston guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company

Complete Address: 705 Fourth Nat'l Bank Bldg., Wichita, Kansas

Lease Name: Blessing Well No. 11

Location: C SW NE Sec. 33 Twp. 19 Rge. 8 (E) (W) X

County Rice Total Depth 3434' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Livingston was instructed to plug the well as follows:

Circulate heavy mud. Fill hole with mud to 215'. Push
plug and 1/4 sack hulls to 215' and cement with 20 sacks
through drill pipe. Fill hole with mud to 40'. Push plug
and 1/4 sack hulls to 40' and cap hole with 10 sacks.
Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent