



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

April 25, 1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 30 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ray Rice of Sterling Drilling Company has this date requested permission to plug the following described well:

Mr. Rice guarantees payment of the plugging fee.

Operator's full Name: Lobsack Oil Production, Inc.

Complete Address: Box 489, Hays, Kansas 67601

Lease Name: Keens Well No. 1

Location: C SE NW Sec. 28 Twp. 19 Rge. 8 (E) (W) X

County: Rice Total Depth 3488' Oil Well

Gas Well Input Well SWD Well OWWO
D & A X Lost Hole

Mr. Rice was instructed to plug the well as follows:

Fill hole with mud. Push plug and 1/4 sack hulls to 450' and pump 40
sacks cement through drill pipe at 450'. Pump 25 sacks cement through
drill pipe at 190'. Push plug and 1/2 sack hulls to 40' and cap hole
with 10 sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

Conservation Division Agent