

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMM.

MAY 13 1963

5-13-63  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Lillard of Toland Casing Pulling has this date requested permission to plug the following described well:

Mr. Lillard guarantees payment of the plugging fee.

Operator's full Name: Ashland Oil & Refining Co.

Complete Address: Box 949, Liberal, Kansas

Lease Name: Lawrence York Well No. # 1

Location: C SE NW Sec. 6 Twp. 32 Rge. 17 (E)(W) W

County Comanche Total Depth 5981 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Lillard was instructed to plug the well as follows:

570' of 8 5/8" surface pipe, cement circulated with 625

sacks. 5200' of 4 1/2" long string, cemented with 175 sacks.

Plugged back to 5171'. Perferated 5140' to 5123'. Sand

to 5100', cement with 3 sacks. Fill hole with mud to 225'.

10' rock bridge, cement with 20 sacks. Fill hole with mud to 40', 10' rock bridge, cement with 10 sacks to base cellar.

Very truly yours,

Arlie Elving  
 Conservation Division Agent