

State of Kansas



15-033-20155-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 23 1974  
15-23-74  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Hanna of Anadarko Production Company has this date requested permission to plug the following described well:

Mr. Hanna guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name: Brandner Well No. 1

Location: C E/2 NE Sec. 25 Twp. 31 Rge. (E)(W) 18

County: Comanche Total Depth 5180' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Hanna was instructed to plug the well as follows:

399 ft 8-5/8" surface cemented with 500 sacks. 5179 ft. 4-1/2"

long string cemented with 140 sacks. Top perf. 5087 ft. Pump

40 sacks cement to 4500 ft. Pulled 510 ft 4-1/2. Pump 40 sacks

cement to 350 ft. Mud to 40 ft, plug, 1/2 sack hulls, 20 sacks  
cement to surface. Pumped by Halliburton Cementing, Great Bend, KS.

Very truly yours,

*[Signature]*  
Conservation Division Agent