

State of Kansas



15-833-20375-0000

Form CP-2

JOHN CARLIN
R. C. LOUX
JANE T. ROY
WILLIAM G. GRAY
Carol J. Larson, Executive Secretary

Governor
Chairman
Commissioner
Commissioner

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

APR 25 1980
8-25-80
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Fox of Abercrombie Drlg., Inc. has this date requested permission to plug the following described well:

Mr. Fox guarantees payment of the plugging fee.

Operator's full Name: The Maurice L. Brown Co & Wayne Woolsey.

Complete Address: 200 Sutton Pl., Wichita, Ks. 67202

Lease Name: Loesch Well No. 1-A

Location 20'S & 100'E/C NE NE Sec. 12 Twp. 31s Rge. 18 (E)(W) W

County: Comanche Total Depth Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Fox was instructed to plug the well as follows:

200' 13 3/8" casing w/250 sax cement. 1050' 8 5/8" casing
w/450 sax cement on bottom & 145 sax cement on top-Set 50
sax cement plug at 1020'-Set 50 sax cement plug at 570'-
Bridge at 40' & 1/2 sax cement to 5' below Gl. 5 sax in rat
hole. Cemented by Howco.

Very truly yours,

Conservation Division Agent