



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 28 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Cook of Graham-Michaelis Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Graham-Michaelis Drlg. Co.

Complete Address: 211 N. Broadway Wichita, Ks

Lease Name: Murray-Crawford Well No. 1-16

Location: C NW/NE Sec. 16 Twp. 31s Rge. 18 (E)(W) W

County: Comanche Total Depth 5152 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Cook was instructed to plug the well as follows:

598 ft of 8 5/8 surface pipe cemented with 400 sacks.

Pumped 25 sacks cement to 626 ft. Plug at 283 ft, 25 sacks

cement. Mud to 30 ft, plug, 1/2 sack hulls, 10 sacks cement

to surface. 2 sacks cement in rat hole.

Very truly yours,

M. Russell Bikerstein  
Conservation Division Agent