

State of Kansas



15-033-30003-0000

FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 27 1965

7-27-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Frank Musgrove of Hellar Drilling Company has this date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: William H. Pine

Complete Address: McCulloch Bldg., Okmulgee, Oklahoma

Lease Name: Robinson Well No. # 1-A

Location: 140' NW/C NW NE Sec. 5 Twp. 31 Rge. 18(E) (W) W

County Comanche Total Depth 5088' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Musgrove was instructed to plug the well as follows:

612' of 10 3/4" surface pipe, cement circulated with 300 sacks.  
Fill hole with drilling mud to 350', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling  
mud to 40', 2nd cementing plug, bridge with hulls, and cement  
with 10 sacks to base cellar. Bridge and cement rat hole with  
.2 sacks.

Very truly yours,

*Archie Elving*