

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 1 1974
10-1-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Fraizer of Cities Service Co has this

date requested permission to plug the following described well:

Mr. Fraizer guarantees payment of the plugging fee.

Operator's full Name: Cities Service Co

Complete Address: 700 Sutton Place Wichita, KS

Lease Name: Toothaker A Well No. 1

Location: C SW/SW Sec. 2 Twp. 31s Rge. 18 (E)(W) W

County: Comanche Total Depth 5110 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Frazier was instructed to plug the well as follows:

352 ft 13 3/8 surface cement circulated. 1107 ft 8 5/8

surface cemented with 300 sacks. Pump plug, 40 sacks

cement to 800 ft. 2nd plug at 325 ft, 25 sacks cement.

Mud to 40 ft, plug, 1/2 sack hulls, 10 sacks cement to

surface. 2 sacks cement in rat hole.

Pumped by Halliburton Cementing Great Bend, KS
Very truly yours,

Conservation Division Agent