

State of Kansas



15-033-20170-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION

10 4 1975 2-4-75 CONSERVATION DIVISION Wichita, Kansas

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Frazey of Cities Service Oil has this date requested permission to plug the following described well:

Mr. Frazey guarantees payment of the plugging fee.

Operator's full Name: Cities Services Oil Co

Complete Address: 700 Sutton Place Wichita, KS

Lease Name: Herrington A Well No. 1

Location: 1855' FEL & 1980' FNL Sec. 2 Twp. 31s Rge. 18 (E)(W) W

County: Comanche Total Depth 5100 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Frazey was instructed to plug the well as follows:

230 ft 13 3/8 surface cemented with 400 sacks. 1015 ft 8 5/8 surface cemented with 400 sacks. Pump plug, 25 sacks cement to 1000 ft. 2nd plug at 225 ft, 25 sacks cement. Mud to 40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface. 2 sacks cement in rat hole.

Pumped by Halliburton Cementing, Great Bend, KS

Very truly yours,

[Signature] Conservation Division Agent