

State of Kansas



15-033-20195-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

4-8-76

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Glenn of Pine Pullers Inc has this

date requested permission to plug the following described well:

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc

Complete Address: Route 2 Great Bend, KS

Lease Name: Delaney Well No. 1

Location: C SE/NW Sec. 36 Twp. 31 Rge. 18 (E)(W) W

County: Comanche Total Depth 5177 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Glenn was instructed to plug the well as follows:

609 ft 8 5/8 surface cemented with 600 sacks. 5146 ft

5 1/2 long string cemented with 125 sacks. Top perf. 5131 ft.

Open hole. Sand, 5 sacks cement to 5100 ft. Pulled 4312

ft 5 1/2. Set 20 ft rock bridge at 320 ft. Fill hole with

5 yds redimix to surface.

Very truly yours,

Conservation Division Agent