

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-20869-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 35-23S-4W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: B MCELWAIN Well #: 1A
County: RENO Total Vertical Depth: 3400 feet

Operator License No.: 33324
Op Name: ALLAM PRODUCTION, INC.
Address: PO BOX 2325
HUTCHINSON, KS 67504

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3311	543	100 SX
SURF	12.75	265		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/27/2014 4:00 PM
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.
Proposal Rcvd. from: WR ALLAM Company: _____ Phone: (620) 663-7813

Proposed Plugging Method: Plug bottom off with sand and cement. Shoot pipe off at 600 ft an plug back to surface.

Plugging Proposal Received By: PATRICK SHIELDS WitnessType: PARTIAL
Date/Time Plugging Completed: 03/27/2014 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 2925', CAPPED WITH 5 SXS CEMENT ON TOP. CUT CASING PIPE OFF @ 543' PULLED CASING. RAN TUBING INTO 555' SPOTTED 50 SXS CEMENT WAITED 2 HOURS. TAGGED TOC @ 350'. RAN TUBING INTO 306' CIRCULATED TO SRUFACE WITH 300 SXS CEMENT. 3-28-14 CHECKED TOP PLG, AT SURFACE. CLOSED.

Perfs:

KCC WICHITA
APR 29 2014
RECEIVED

Remarks: COPELAND CEMENTING OUT OF BURRTON, 60/40 4% POS MIX, TICKET #40814. PAST TEN YEARS WITHOUT TA OR PRODUCTION.

Plugged through: CSG

District: 02

Signed B. J. Hope
5/02/14
(TECHNICIAN)

1/2K