

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-21376-00-00
Spot: E2NE Sec/Twnshp/Rge: 32-18S-21W
4161 feet from S Section Line, 679 feet from E Section Line
Lease Name: SCHNIEPP Well #: 1
County: NESS Total Vertical Depth: 4231 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1331		CMT TO SURFACE
PROD	5.5	4216	0	WITH 150 SX CMT
SURF	8.625	295		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/16/2014 8:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: PUMP 50 SX CMT & 150# HULLS, THEN GEL SPACER TO 1400' THEN CMT TO SURFACE. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/16/2014 12:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RAN BOND LOG & FOUND CMT FROM 1331' TO SURFACE, SHOWED DV TOOL. TIED ONTO CASING & PUMPED 80 SX CMT & 300# HULLS, THEN GEL SPACER TO 1400', THEN 125 SX CMT. PRESSURED TO 900#. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 500#.

Perfs:

Top	Bot	Thru	Comments
4216	4231	OH	

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

KCC WICHITA

APR 28 2014

RECEIVED

District: 01

Signed Michael Maier
5/02/14 (TECHNICIAN)

RECEIVED

APR 21 2014

KCC DODGE CITY