

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-21448-00-00
Spot: S2NE Sec/Twnshp/Rge: 32-18S-21W
3364 feet from S Section Line, 1322 feet from E Section Line
Lease Name: SCHNIEPP Well #: 2
County: NESS Total Vertical Depth: 4228 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	4150		WITH 2 SX CMT
DVT		1306		CMT TO SURFACE
PROD	5.5	4223	0	WITH 150 SX CMT
SURF	8.625	290		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/16/2014 8:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: RUN CIBP 50' ABOVE PERFS. RUN TBG & CIRCULATE CMT FROM 1350' TO SURFACE. PUMP 50 SX CMT DOWN BACKSIDE IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/16/2014 3:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4150' WITH 2 SX CMT. RAN BOND LOG & FOUND DV TOOL @ 1306' & CMT TO SURFACE. RUN TBG TO 1395' & PUMPED 125 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 25 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4223	4228	OH	

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

KCC WICHITA
APR 28 2014
RECEIVED

District: 01

RECEIVED

APR 21 2014

KCC DODGE CITY

Signed

Michael Maier
5/02/14

(TECHNICIAN)