

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24150-00-00
Spot: N2SWNWNW Sec/Twnshp/Rge: 33-18S-21W
829 feet from N Section Line, 351 feet from W Section Line
Lease Name: SCHNEIPP B Well #: 1
County: NESS Total Vertical Depth: 4301 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4150		WITH 2 SX CMT
DVT		1356		WITH 225 SX CMT
PROD	5.5	4321	0	WITH 325 SX CMT
SURF	8.625	323		WITH 220 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/16/2014 8:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: RUN CIBP 50' ABOVE PERFS. RUN TBG & CIRCULATE CMT FROM 1350' TO SURFACE. PUMP 50 SX CMT DOWN BACKSIDE IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/16/2014 10:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

SET CIBP @ 4150' WITH 2 SX CMT. RUN TBG TO 1395'. PUMP 130 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 500# & HELD.

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

KCC WICHITA
APR 28 2014
RECEIVED

District: 01

Signed Michael Maier
5/02/14 (TECHNICIAN)

RECEIVED
APR 21 2014
KCC DODGE CITY