

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-20390-00-01  
Spot: SWNWNE Sec/Twnshp/Rge: 10-32S-7E  
4290 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: BEAMER Well #: 15  
County: COWLEY Total Vertical Depth: 2902 feet

Operator License No.: 33711  
Op Name: B-C STEEL, LLC  
Address: 1432 NIGHTHAWK RD  
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2902		150 SX
SURF	8.625	205		0 SX

Well Type: EOR UIC Docket No: E06951.9 Date/Time to Plug: 02/14/2014 8:00 AM  
Plug Co. License No.: 34685 Plug Co. Name: RCCA WELL SERVICE, LLC  
Proposal Rcvd. from: ROGER ALTIS Company: RCCA WELL SERVICE Phone: (620) 583-5545

Proposed Plugging Method: AS PER KCC RULES & REGS/ CMT BACK TO 2080, 255'-0'', CIRC TO SURFACE.

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/14/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SHOT SQUEEZE HOLES @ 255' - 256' (2 HOLES). RIH W/TBG @ 2100', RCCA ESTABLISHED CIRCULATION, MIXED & PUMPED 22 SXS CLASS A COMMON & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT PLUG @ 1980'. PRESSURED WELL @ 400#, WELL WOULD NOT CIRCULATE ON BACKSIDE. RIH ON WIRELINE, SHOT SQUEEZE HOLES @ 230'-231' (4 HOLES). WELL WOULD NOT CIRCULATE, RIH W/TBG @ 372' INSIDE CASING, & 22' OUTSIDE CASING. RCCA MIXED & PUMPED 82 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 2-14-2014.

Perfs:

Top	Bot	Thru	Comments
2130	2140		CSG

Remarks: FAILED MIT/ COMPLIANCE

Plugged through: TBG

KCC WICHITA

APR 28 2014

RECEIVED

District: 02

Signed

*Duane Krueger*  
(TECHNICIAN)  
5/02/14  
cc to WC 5/02/14

1/4