

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-21653-00-00  
Spot: SESENE Sec/Twnshp/Rge: 16-26S-7E  
2970 feet from S Section Line, 330 feet from E Section Line  
Lease Name: CHARVAT A Well #: 1  
County: BUTLER Total Vertical Depth: 2820 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2819		100 SX
SURF	8.625	200		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/27/2014 8:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: GEORGE RAYL Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed  
Plugging  
Method:

AS PER KCC RULES & REGS / CIBP @ 2750 W/4 SXS / PERF & CIRC 250'-0'

Plugging Proposal Received By: DUANE KRUEGER  
Date/Time Plugging Completed: 02/27/2014 11:40 AM

WitnessType: NONE  
KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2720', DUMP BAILED 4 SXS ON TOP. RIH ON WIRELINE, SHOT SQUEEZE HOLES @ 250'-251' (2 HOLES). RIH W/TBG @ 250', GRESSEL OILFIELD ESTABLISHED CIRCULATION, MIXED & PUMPED 120 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. PLUG DOWN 11:40 AM 2-26-2014. CEMENT TICKET #40790.

Perfs:

Top	Bot	Thru	Comments
2771	2774	CSG	

Remarks:

Plugged through:

KCC WICHITA

APR 28 2014

RECEIVED

District: 02

Signed

DUANE KRUEGER  
3/07/14  
(TECHNICIAN)