

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-20528-00-00
Spot: E2SESW Sec/Twnshp/Rge: 16-23S-3W
660 feet from S Section Line, 2310 feet from W Section Line
Lease Name: SIEMANS Well #: 1
County: HARVEY Total Vertical Depth: 3360 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3357		75 SX
SURF	8.625	341		300 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/31/2014 12:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: GEORGE RAYL Company: GRESSEL OILFIELD SERVICE Phone: (316) 524-1225

Proposed
Plugging
Method:

According to the rules and regulations of the KCC. Note - Junk in hole @ 1771'.

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 01/31/2014 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

JUNK IN HOLE @ 1771'. RAN TUBING INTO 2390' SPOTTED 90 SXS CEMENT.
PERFORATED @ 550 WITH 4 SHOTS, RAN TUBING INTO 570' SPOTTED 35 SXS OF
COMMON CEMENT WITH 3% CC, TAGGED TOC @ 410'. PERFORATED CASING @
390' WITH 4 SHOTS, CIRCULATED TO SURFACE WITH 165 SXS OF 60/40 4%.

Perfs:

Top	Bot	Thru	Comments
3263	3290		

KCC WICHITA
APR 29 2014
RECEIVED

Remarks: COPELAND CEMENTING BURTON, 60/40 4% POS MIX, TICKET #40785: JUNK IN HOLE

Plugged through: TBG

District: 02

Signed

B. J. Hope
5/02/14

(TECHNICIAN)