

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21080-00-01
Spot: NESWNWNE Sec/Twnshp/Rge: 12-20S-6W
4313 feet from S Section Line, 2268 feet from E Section Line
Lease Name: COUP B Well #: 2
County: RICE Total Vertical Depth: 3429 feet

Operator License No.: 5610
Op Name: BRUCE OIL COMPANY, L.L.C.
Address: 1704 LIMESTONE RD
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3429	1450	200 SX
SURF	8.625	324		200 SX

Well Type: EOR UIC Docket No: E24311.1 Date/Time to Plug: 04/10/2014 1:00 PM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: BUD DAVIS Company: SUNFLOWER WELL SERVICE, INC. Phone: (620) 628-4723

Proposed Plugging Method: AS PER KCC RULES & REGS. WELL FAILED ON 1-10-2104. CP1 INDICATES CASING LEAK @ 1450'.

Plugging Proposal Received By: HUNTER CLARK WitnessType: PARTIAL
Date/Time Plugging Completed: 04/10/2014 4:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL TUBING OUT. SAND PERFS TO 3280' AND CAP WITH 5 SX'S CEMENT. CUT CASING OFF @ 1450' AND PUMP 35 SX'S CEMENT. PULL CASING TO 850' AND PUMP 35 SX'S CEMENT WITH CC. PULL CASING ON UP TO 450'. LET SET A WHILE-TAG CEMENT @ 800' WITH SAND LINE BAILER. CIRCULATE CEMENT FROM 450' TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3333	3386	CSG	

KCC WICHITA
APR 29 2014
RECEIVED

Remarks: 60 40 POZ 4% GEL. CONSOLIDATED TICKET #45134 -- FAILED MIT CASING LEAK @ 1450'.

Plugged through: CSG

District: 02

Signed Virgil Clothier
5/02/14 (TECHNICIAN)

cc to UIC 5/02/14

14