

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22768-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 28-19S-10W
1650 feet from N Section Line, 330 feet from W Section Line
Lease Name: CEMETARY Well #: C-2
County: RICE Total Vertical Depth: 3360 feet

Operator License No.: 6768
Op Name: CARRIE EXPLORATION & DEVELOPM
Address: 210 W 22ND
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	272		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/27/2014 8:00 AM
Plug Co. License No.: 34908 Plug Co. Name: SKYTOP DRILLING LLC
Proposal Rcvd. from: TOM ENGEL Company: _____ Phone: _____

Proposed Plugging Method: SPOT 35 SXS @ TOP OF ARBUCKLE FORMATION, SPOT 35 SXS BOTTOM SALT PLUG @ 1250', SPOT A 35 SXS TOP SALT PLUG @ 900', SPOT A 35 SX PLUG 50' BELOW BOTTOM OF SURFACE CASING, PULL PIPE TO 60' AND 25 SXS CIRCULATE OUT OF HOLE. 25 SXS IN RATHOLE, 20 SXS IN MOUSE HOLE. 60X40 POZ < 4% GEL.

Plugging Proposal Received By: PATRICK SHIELDS WitnessType: NONE
Date/Time Plugging Completed: 03/27/2014 8:00 AM KCC Agent: PATRICK SHIELDS

Actual Plugging Report: _____ Perfs: _____
SURFACE CASING SET @ 272', TD @ 3360', TOP OF ARBUCKLE AT 3284'. 35 SXS @ 3284' (ARB), 35 SXS @ 1250' (BOS), 35 SXS @ 900' (TOS), 35 SXS @ 320' (BOSC), CIRCULATED 25 SXS FROM 60' TO SURFACE. 25 SXS IN RATHOLE, 20 SXS IN MOUSE HOLE.

Remarks: CEMENT FROM BASIC 60X40 POZ < 4% GEL.

Plugged through: DP

KCC WICHITA
APR 28 2014
RECEIVED

District: 02

Signed [Signature]
5/02/14 (TECHNICIAN)

✓