

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-30072-00-00  
Spot: SWNW Sec/Twnshp/Rge: 6-33S-16W  
3300 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: GREGG Well #: 1  
County: COMANCHE Total Vertical Depth: 5082 feet

Operator License No.: 31021  
Op Name: CASTELLI EXPLORATION, INC.  
Address: 6908 W 112TH  
OKLAHOMA CITY, OK 73162

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		930		
CIBP		5010		WITH 2 SX CMT
PROD	4.5	5081	0	WITH 125 SX CMT
SURF	8.625	411		WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/15/2014 1:00 PM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 5010' WITH 2 SX CMT. CIBP @ 930'. RUN TBG & CIRCULATE CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/15/2014 3:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5010' WITH 2 SX CMT. SET CIBP @ 930'. PERFORATED AT 900'. RAN TBG TO 900' & PUMPED 175 SX 60/40 POZMIX 4% GEL FOLLOWED BY 55 SX COMMON CEMENT, CIRCULATING CMT UP BOTH SIDE OF THE PRODUCTION CASING. PULLED TBG OUT OF THE HOLE & TOPPED OFF WITH 5 SX CMT. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5062	5072		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

KCC WICHITA

APR 28 2014

RECEIVED

District: 01

RECEIVED

APR 22 2014

KCC DODGE CITY

Signed

*Eric MacLaren*  
*5/02/14*

(TECHNICIAN)