

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19183-00-00
Spot: NWSENESW Sec/Twnshp/Rge: 17-25S-5E
1799 feet from S Section Line, 3049 feet from E Section Line
Lease Name: L W ROBISON SOUTH Well #: 2B
County: BUTLER Total Vertical Depth: 721 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	696		0 SX
SURF	8.625	205		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/25/2014 8:00 AM
Plug Co. License No.: 31538 Plug Co. Name: BURKHOLDER, STEVE DBA HAD-A-CALL OIL
Proposal Rcvd. from: DALLAS FLOWERS, CROW Company: CROWN ENERGY Phone: (316) 323-3869

Proposed Plugging Method: AS PER KCC RULES & REGS / SAND 2 645 W/7 SXS / PERF 255 & CIRC TO SURFACE

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/25/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 715', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL, 75# POLYFLAKE & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 630'. RIH ON WIRELINE, SHOT SQUEEZE HOLES @ 255'-256' (4 HOLES). SWEDGED INTO 7" CASING, ESTABLISHED CIRCULATION, CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 80 SXS 60/40 POZMIX 4% GEL 1% CC TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 2/25/2014. CEMENT TICKET #42917.

Perfs:

Top	Bot	Thru	Comments
696	721	OH	

KCC WICHITA

Remarks: COMPLIANCE / DENIED TA

Plugged through: TBG

APR 28 2014
RECEIVED

District: 02

Signed

DUANE KRUEGER
5/02/14 (TECHNICIAN)

✓