

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19321-00-00
Spot: NWSESWSE Sec/Twnshp/Rge: 35-25S-4E
330 feet from S Section Line, 1704 feet from E Section Line
Lease Name: RICE-PARMELEE Well #: 1
County: BUTLER Total Vertical Depth: 2430 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2407		0 SX
SURF	8.625	200		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/25/2014 8:00 AM
Plug Co. License No.: 31538 Plug Co. Name: BURKHOLDER, STEVE DBA HAD-A-CALL OIL
Proposal Rcvd. from: DALLAS FLOWERS, CROW Company: CROWN ENERGY CO. Phone: (316) 323-3869

Proposed Plugging Method: SAND @ 2355 W/5 SXS / PERFORATE & CIRC 250'-0'.

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/25/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2400', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 35 SXS 60/40 POZMIX 4% CC. 75# POLY FLAKE & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT PLUG @1400'. TESTED CASING. HELD OK. RIH ON WIRELINE SHOT SQUEEZE HOLES @ 250'-251' (4 HOLES). SWEDGED INTO 5 1/2" CASING, ESTABLISHED CIRCULATION. CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 115 SXS 60/40 POZMIX 4% GEL, 1% CC TO SURFACE. CEMENT CIRCULATED. CONSOLIDATED TICKET # 42916.

Perfs:

Top	Bot	Thru	Comments
2415	2430	OH	

Remarks: COMPLIANCE/DENIED TA

Plugged through: TBG

KCC WICHITA

APR 28 2014

RECEIVED

District: 02

Signed

DUANE KRUEGER
5/02/14 (TECHNICIAN)

1/4