

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23239-00-00
Spot: NESWSWNE Sec/Twnshp/Rge: 33-19S-12W
2300 feet from N Section Line, 2000 feet from E Section Line
Lease Name: WIRTZ Well #: 9
County: BARTON Total Vertical Depth: 3460 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATIO
Address: 7060 S YALE # 702
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3502		150 SX
SURF	8.625	315		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/17/2014 12:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: JOHN MICKLE Company: EAGLE RIVER ENERGY CORP. Phone: (620) 282-9034

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 13 sx gel and 500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/17/2014 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1350', 625' and 300'.
Ran tubing to 3300' and pumped 14 sx gel followed by 75 sx cement w/100 # hulls. Pulled tubing to 1350' and pumped 70 sx cement w/100 # hulls. Pulled tubing to 700' and pumped 40 sx cement w/100 # hulls. Pulled tubing to 350'. Circulated cement to surface with 50 sx cement. Pumped 60 sx cement down and cement did not circulate out to surface when pressured up to 400 psi. Pulled tubing.
04/18/2014- Cut casing and surface below ground level. Ran 1" pipe down between surface pipe and casing to 100'. Circulated cement to surface with 50 sx cement.

GPS: 38.38443 -098.88064

Perfs:

Top	Bot	Thru	Comments
3420	3420		
3296	3346		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

KCC WICHITA

APR 30 2014

RECEIVED

District: 04

Signed Bruce Rodie
5/02/14 (TECHNICIAN)

CM

APR 25 2014