

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-21641-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 25-22S-15W  
1814 feet from S Section Line, 2185 feet from W Section Line  
Lease Name: BLACKWELL/PETERSON Well #: 1-25  
County: PAWNEE Total Vertical Depth: 4200 feet

Operator License No.: 5056  
Op Name: F. G. HOLL COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3750		
CIBP		3975		
PROD	4.5	4192	2675	WITH 225 SX CMT
SURF	8.625	944		WITH 400 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/16/2014 2:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 3630' & 4 SX CMT. PLUG AT 970' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/16/2014 5:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

BRIDGE PLUG @ 3975'. BRIDGE PLUG AT 3750' WAS NOT THERE. SANDED TO 3610' WITH 4 SX CMT. 1ST PLUG AT 980' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 410' WITH 50 SX CMT. 3RD PLUG AT 41' WITH 30 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
3784	3794		
3757	3794		
3688	3692		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

KCC WICHITA  
APR 28 2014  
RECEIVED

District: 01

RECEIVED

APR 22 2014

KCC DODGE CITY

Signed

*Richard W. Lacey*  
3/22/14

(TECHNICIAN)

PM