

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22955-00-00
Spot: E2SWSESE Sec/Twnshp/Rge: 4-14S-14W
330 feet from S Section Line, 880 feet from E Section Line
Lease Name: KRUG C Well #: 7
County: RUSSELL Total Vertical Depth: 3300 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3273		150 SX
SURF	8.625	223		140 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/23/2014 8:30 AM
Plug Co. License No.: 5135 Plug Co. Name: FARMER, JOHN O., INC.
Proposal Rcvd. from: VAL DREHER Company: J & M WELL SERVICE Phone: (785) 483-8356

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/300 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/23/2014 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 200', 830' and 1200'. Ran tubing to 2950' and pumped 100 sx cement w/50 # hulls. Pulled tubing to 1430' and pumped 85 sx cement. Cement circulated. POOH. Hooked to casing and pumped 10 sx cement at 300 psi and shut in. Hooked to braden head and pumped cement to 350 psi.

GPS: 38.85727 -098.87618

Perfs:

Top	Bot	Thru	Comments
2888	2890		
2878	2882		

Remarks: QUALITY CEMENTING TICKET # 110

Plugged through: CSG

KCC WICHITA

APR 30 2014

RECEIVED

District: 04

Signed

Ray A. Dinkel
5/02/14
(TECHNICIAN)

CM

APR 25 2014