

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24935-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 20-19S-14W  
330 feet from S Section Line, 330 feet from W Section Line  
Lease Name: LEROY B Well #: 1  
County: BARTON Total Vertical Depth: 3634 feet

Operator License No.: 7383  
Op Name: GRADY BOLDING CORPORATION  
Address: 114 NORTH MAIN P.O. BOX 486  
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3629	2400	125 SX
SURF	8.625	827		400 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/16/2014 1:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: GRADY BOLDING Company: GRADY BOLDING CORP. Phone: (620) 564-2240

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/16/2014 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with cement.  
Cut casing at 2400'. Pulled casing to 1450' and pumped 125 sx cement w/200 # hulls. Pulled casing to 850' and pumped 60 sx cement w/100 # hulls. Pulled casing to 400'. Circulated cement to surface with 100 sx cement and 150 # hulls. Pulled casing and hole stayed full.

GPS: 38.37711 -098.90250

Perfs:

Top	Bot	Thru	Comments
3550	3554		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

KCC WICHITA

APR 30 2014

RECEIVED

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

✓ 5/02/14

CM

APR 25 2014