

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20693-00-00
Spot: SWSNWNE Sec/Twnshp/Rge: 29-4S-22W
1305 feet from N Section Line, 1972 feet from E Section Line
Lease Name: SPROUL Well #: 29-1
County: NORTON Total Vertical Depth: 3793 feet

Operator License No.: 30535
Op Name: HARTMAN OIL CO., INC.
Address: 10500 E BERKELEY SQ PKWY STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	352		225 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/18/2014 12:00 AM
Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC
Proposal Rcvd. from: STEVE Company: H2 DRILLING LLC Phone: (620) 770-2214

Proposed Plugging Method: Ordered 270 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB Witness Type: NONE
Date/Time Plugging Completed: 04/18/2014 12:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

1st plug @3703 w/50 sx
2nd plug @1936 w/25 sx
3rd plug @1149 w/100 sx
4th plug @402 w/40 sx
5th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: ALLIED

Plugged through: DP

KCC WICHITA
APR 30 2014
RECEIVED

District: 04

Signed _____

[Signature]
5/27/14 (TECHNICIAN) CM

APR 25 2014