

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-00252-00-00
Spot: SWNE Sec/Twnshp/Rge: 27-32S-40W
3348 feet from S Section Line, 1987 feet from E Section Line
Lease Name: MYERS GAS UNIT B Well #: 1
County: MORTON Total Vertical Depth: 5574 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5236		WITH 2 SX CMT
CIBP		5395		
PROD	4.5	5557	1003	WITH 550 SX CMT
SURF	10.75	701		WITH 650 SX CMT

Well Type: GAS UIC Docket No: Date/Time to Plug: 03/31/2014 1:00 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (620) 275-2963

Proposed Plugging Method: SET CIBP @ 5166' WITH 2 SX CMT. PLUG AT 1560' WITH 50 SX CMT. PLUG AT 730' WITH 80 SX CMT. PLUG AT 40' WITH 40 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS Witness Type: PARTIAL
Date/Time Plugging Completed: 04/01/2014 12:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5236' WITH 2 SX CMT. STRETCH SHOWED ~1000' OF FREE PIPE. PIPE WAS SHOT OFF AT 1003'. 1ST PLUG AT 730' WITH 80 SX CMT. PLUG DID NOT HOLD & WENT DOWN HOLE. 4/1/14: TAGGED HEAVY MUD AT 760' WITH SLICK LINE & SINKER BAR. LOADED HOLE WITH MUD & PUMPED 80 SX CMT WITH FULL RETURNS. PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5439	5453		
5286	5359		

KCC WICHITA
APR 21 2014
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed Kenny M Sullivan (TECHNICIAN)
4/2/14

RECEIVED

APR 15 2014

KCC DODGE CITY