

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03292-00-00
Spot: SENENW Sec/Twnshp/Rge: 12-10S-20W
990 feet from N Section Line, 2310 feet from W Section Line
Lease Name: DESBIEN C A Well #: 4
County: ROOKS Total Vertical Depth: 3762 feet

Operator License No.: 34506
Op Name: EMPIRE ENERGY E&P, LLC
Address: 345 RIVERVIEW ST., STE 540
WICHITA, KS 67203

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3754		200 SX
SURF	10.75	334		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/10/2014 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: RANDY WEIGEL Company: EMPIRE ENERGY Phone: (785) 737-3736

Proposed Production perforations; 3498' - 3667'
Plugging Loc set Pkr: Milled over at 3450' and pushed to 3530'
Method: Squeezed at 700' - 900' w/250 sx cement
Squeezed at 1210 w/ 175 sx. Drilled out and plugged well.
Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/10/2014 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing and tagged Loc set packer at 3530'. Pulled tubing to 3520'. Consolidated pumped 50 sx cement. Pulled tubing to 3196' and pumped 150 sx cement w/300 # hulls. Pulled tubing to 1664' and pumped 140 sx cement w/200 # hulls. Circulated cement. PTOH. Topped off 5 1/2" casing w/15 sx cement. Casing full. Hooked up to back side with instant pressure.

Perfs:

Remarks: CONSOLIDATED

Plugged through: TBG

KCC WICHITA
APR 23 2014
RECEIVED

District: 04

Signed Richard Williams
4/24/14 (TECHNICIAN)

CM

APR 15 2014