

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24796-00-01
Spot: SWNENENE Sec/Twnshp/Rge: 29-20S-14W
4941 feet from S Section Line, 557 feet from E Section Line
Lease Name: BARNES TRUST Well #: 1-29
County: BARTON Total Vertical Depth: 3775 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3770	2235	150 SX
SURF	8.625	868		325 SX

Well Type: SWD UIC Docket No: D28675.0 Date/Time to Plug: 04/11/2014 11:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ROB LONG Company: F.G. HOLL CO. Phone: (620) 793-2703

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/11/2014 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

04/10/2014- Sanded back TD to 3546' plus 5 sx cement on top.
04/11/2014- Cut pipe at 2235'. Pulled casing to 1500' and pumped 125 sx cement w/200 # hulls. Pulled casing to 868' and pumped 75 sx cement w/100 # hulls. Pulled casing to 500' and pumped 75 sx cement w/100 # hulls. Pulled casing to 200' and pumped 70 sx cement to fill cellar. POOH and cellar stayed full.

GPS: 38.28918 -098.88664

Perfs:

Top	Bot	Thru	Comments
3620	3630		ARBUCKLE

KCC WICHITA

APR 23 2014

RECEIVED

Remarks: QUALITY WELL SERVICE TICKET # 6166

Plugged through: CSG

District: 04

Signed Ray A Dinkel
4/24/14 (TECHNICIAN) CM

✓ ce to LLC 4/23/14