

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24908-00-01
Spot: N2N2SWSE Sec/Twnshp/Rge: 29-20S-14W
1220 feet from S Section Line, 1980 feet from E Section Line
Lease Name: BARNES TRUST A Well #: 1-29
County: BARTON Total Vertical Depth: 3800 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3788	2170	150 SX
SURF	8.625	878		335 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/10/2014 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ROB LONG Company: F. G. HOLL CO. Phone: (620) 793-0915

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/10/2014 12:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

04/09/2014- Sanded off bottom to 3560' and spotted 5 sx cement on top.
04/10/2014- Cut casing at 2170' and pulled to 1500'. Pumped 125 sx cement w/200 # hulls.
Pulled casing to 870' and pumped 75 sx cement w/100 # hulls. Pulled casing to 500' and pumped 75 sx cement w/100 # hulls. Pulled casing to 300' and pumped 50 sx cement.
Circulated cement to surface. POOH and filled casing and cellar w/20 sx cement. Cellar stayed full.
GPS: 38.27909 -098.89208

Perfs:

Top	Bot	Thru	Comments
3655	3666		
3649	3655		
3644	3647		
3637	3642		
3632	3637		
3626	3666		ARBUCKLE

Remarks: QUALITY WELL SERVICE TICKET # 6165

Plugged through: CSG

KCC WICHITA

APR 23 2014

RECEIVED

District: 04

Signed

Ray A Dinkel
4/24/14

(TECHNICIAN)

CM