

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-125-30465-00-00  
Spot: NWNWSWNE Sec/Twnshp/Rge: 31-34S-14E  
3675 feet from S Section Line, 2333 feet from E Section Line  
Lease Name: BURROWS Well #: 1-31  
County: MONTGOMERY Total Vertical Depth: 1541 feet

Operator License No.: 33850  
Op Name: CANEY VALLEY DISPOSAL, LLC  
Address: 1870 CR 1900  
CANEY, KS 67333

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1535		230 SX
SURF	8.625	45		8 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/22/2014 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: LARRY SOLES Company: \_\_\_\_\_ Phone: (620) 870-9684

Proposed Plugging Method: Run 1" tubing to bottom. Place 50' cement plug from 1535 to 1485'. Place 50' cement plug from 749 to 699'. Fill with cement from 350 to surface. Cut casing below ground level. Restore location.

Plugging Proposal Received By: STEVE KORF Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/18/2014 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1520' gelled hole and spotted 10 sack plug. Pulled up to 750' and spotted 10 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 55 sacks of cement were used to plug this well.

Perfs:

RECEIVED  
APR 22 2014  
KCC Chanute Dist. #3

DS

Remarks:

Plugged through: TBG

District: 03

Signed

  
4/28/14 (TECHNICIAN)  
KCC WICHITA

APR 24 2014

RECEIVED