

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-02395-00-00  
Spot: W2SEENENW Sec/Twnshp/Rge: 23-26S-14E  
4290 feet from S Section Line, 3135 feet from E Section Line  
Lease Name: LOUK Well #: 7  
County: WOODSON Total Vertical Depth: 1303 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1300		200 SX
SURF	8	22		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/08/2014 10:00 AM  
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC  
Proposal Rcvd. from: REX ASHLOCK Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: COMPANY UNIT RUN IN 2" TBG TO TD ELITE CEMENT & ACID SERVICE ESTABLISH CIRCULATION GEL HOLE TO SURFACE. PUMP 250' CEMENT AT 1303' COMPANY UNIT PULL TBG UP TO 500' ELITE PUMP 50' CEMENT. COMPANY UNIT PULL TBG UP TO 250' ELITE PUMP CEMENT TO SURFACE. COMPANY UNIT PULL TBG OUT ELITE TOP WELL OFF AT SURFACE. WILL GO BACK LATER & CUT SURFACE OFF BELOW PLOW DEPTH.

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/08/2014 2:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1303' pumped 250' cement plug, pulled tubing to 500' pumped 50' cement plug, pulled tubing to 250' pumped cement to surface gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
1236	1262		

RECEIVED  
APR 21 2014  
KCC Chanute Dist. #3  
MH

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern  
4/28/14 (TECHNICIAN)

KCC WICHITA

APR 24 2014

RECEIVED