

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - -

RECEIVED
STATE CORPORATION COMMISSION
(for this well)

AUG 06 1976
8-6-76
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Clarke Corporation

Complete Address 107 W Fowler Medicine Lodge, KS

Lease Name Eden Well No. 1

Location C SE/NE Sec. 31 Twp. 32 Rge. 16 (E) (W) W

County Comanche Total Depth 5050

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Clarke Corporation

Address 107 W Fowler Medicine Lodge, KS License No. 583

Operation Completed: Hour 11:00 AM Day 5 Month 8 Year 1976

The above well was plugged as follows:

240 ft 8 5/8 surface cement circulated. 4900 ft 2 7/8 tubing long
string cemented with 50 sacks. No perf. Sand to 4860 ft, 4 sacks
cement with bailer. Pulled 3000 ft 2 7/8" tubing. Set 10 ft rock
bridge at 220 ft, 25 sacks cement. Mud to 40 ft, plug, 1/2 sack hulls,
10 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed [Signature]
Well Plugging Supervisor

DATE 8-6-76

INV. NO. 3588-W