

KANSAS

JL
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 11 1972
8-11-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Hershberger Explorations Inc.
Complete Address Suite 230 Garvey East 200 W Douglas Wichita, Ks
Lease Name Yost Well No. 1
Location NW/NW/SE Sec. 31 Twp. 31 Rge. 18 (E) W
County Comanche Total Depth 5397
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Clarke Oilfield Service
Address 107 W Fowler Medicine Lodge, Ks License No. 583
Operation Completed: Hour 4:00 PM Day 10 Month 8 Year 1972

The above well was plugged as follows:

419 ft 8 5/8 surface pipe cement circulated. 5394 ft 4 1/2 long string
cemented with 200 sacks. Top perf. 5190 ft. Sand to 5180 ft, 4 sacks
cement with bailer. Pulled 3000 ft 4 1/2. Set 10 ft rock bridge at
200 ft with 25 sacks cement. Mud to 40 ft, 10 ft rock bridge, 10
sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Russell Schuster*
Well Plugging Supervisor

DATE 8/11/72
INV. NO. 6149-11