

KANSAS

JP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
APR 25 1966
4-25-66
KANSAS STATE CORPORATION COMMISSION
WICHITA, KANSAS

Operator's Full Name Aladdin Petroleum Corporation

Complete Address: 809 Petroleum Bldg., Wichita, Kansas

Lease Name Alexander Well No. # 1

Location SE SE SE Sec. 8 Twp. 32 Rge. 19 (E) (W) W

County Comanche Total Depth 5312'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Washedown

Other well as hereafter indicated: _____

Plugging Contractor: Glen & Smith Casing Pulling Company

Address: Box 156, Ellinwood, Kansas License No. 396

Operation Completed: Hour 5:00PM Day 21st Month April Year 1966

The Above well was plugged as follows:

470' of 8 5/8" surface pipe, cement circulated. 5311' of 4 1/2" long string,
cemented with 100 sacks. Plug back T.D. 5250'. Top perforation 5235'.
Bottom of the hole was sanded to 5225', and cemented with 3 sacks.
4741' of 4 1/2" long string was recovered from the hole. Hole was filled
with mud to 300', rock bridge from 300' to 290', and cemented with 25
sacks. Hole was filled with mud to 40', rock bridge from 40' to 30',
and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 4/26/66

INV. NO. 3095-u