

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
4-21-80  
APR 21 1980  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 033-30065-00-00 (of this well)

Operator's Full Name Eason Oil Co.

Complete Address Box 18755-Okla., City, Okla. 73118

Lease Name Schuette Well No. 1

Location NW SE Sec. 1 Twp. 32S Rge. 16 (E) (W)

County Comanche Total Depth 4860

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Jerry Dunkin Casing Pullers.

Address Box 1022-woodward, Okla. 73801 License No. 827

Operation Completed: Hour 1 Pm. Day 18 Month 4 Year 1980

The above well was plugged as follows:

250' 13 3/8" casing. 2400' 8 5/8" casing-5 1/2" casing set at 4860'-  
Preforated at 4760' to 4790'-Mixed & pumped 35 sax common cement  
in 5 1/2" casing, top cement at 4555'-Pull 2904' 5 1/2" casing-Set 35 sax  
cement plug in 8 5/8" casing at 2183'-Pull 725' 8 5/8" casing-Set  
50 sax cement plug in 13 3/8" casing at 240'-Bridge at 40' & 32 sax  
cement to top of casing. Cemented by Dunkin Casing Pullers.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 4-21-80

INV. NO. 1968-w